

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-185-21,228-0000 ✓

245 North Water
Wichita, KS 67202

Operator's Full Name Petroleum, Inc.

Complete Address 800 H.R. Garvey Bldg, Wichita, Kansas 67202

Lease Name Rixon "A" Well No. 3

Location 150' E of C NE SWSW Sec. 7 Twp. 24 Rge. 13 (~~East~~) (West)

County Stafford Total Depth 4186' 136.05

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor B+B Drilling, Inc. and Halliburton Co.

Address 515 Union Center, Wichita, Ks. License No. _____

Operation Completed: Hour: 9:00AM Day: 8 Month: February Year: 1981

The above well was plugged as follows: 8 5/8" - 298' - 225 sacks Common

Hole Filled with mud. 50 sacks Cement pumped through drill pipe at 700'. 25 sacks cement pumped through drill pipe at 290'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 5 sacks cement.

(50-50 Perm mix w/4% gel and 3% Cal. Chloride)

RECEIVED
STATE CORPORATION COMMISSION
2-11-81
FEB 11 1981

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 2-13-81

INV. NO. 4877-W

Signed: _____

CONSERVATION DIVISION
Wichita, Kansas
Conservation Division Agent