

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-5-68
MAR 5 - 1968
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasWell Plugging Authority,
issued January 31, 1968.Operator's Full Name Wichita Iron & Metals Corporation, Inc.Complete Address: Box 13021, Wichita, Kansas 67218Lease Name Koelsch "B" Well No. # 3Location NW NW SW Sec. 11 Twp. 24 Rge. 14 (E) (W) WCounty Stafford Total Depth 4050'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Glenn & Smith Casing Pulling CompanyAddress: Box 156, Ellinwood, Kansas 67526 License No. 396Operation Completed: Hour 11:30AM Day 29th Month February Year 1968

The Above well was plugged as follows:

426' of 8 5/8" surface pipe, cement circulated. 4049' of 5 1/2" long string, cement-
ed with 125 sacks. Plug back T.D. 3850'. Top perforation 3490'. Bottom of the
hole was sanded to 3475', and cemented with 5 sacks, through the dump bailer, with
cement from 3475' to 3435'. 2100' of 5 1/2" long string was recovered from the hole.
Bridge plug was pushed in fluid to 300', bridge plug and rock bridge from 300' to
290'. 5 sacks of cement was mixed in a barrel, and put on plug at 290', through
the dump bailer, and let set over-night. Next day hole was bailed dry, and 20
sacks of cement was added to the plug, with cement from 290' to 215'. Hole was
filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks,
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 3/5/68INV. NO. 7359-W