

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 20 1963  
 9-20-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Buck Smith of Glen & Smith Casing Pull, has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.Operator's full Name: Wilcox Oil Inc.Complete Address: P. O. Box 13528, Phoenix, ArizonaLease Name: Reaves Well No. # 1Location: SW SW NW Sec. 1 Twp. 24 Rge. 16 (E) (W) WCounty Edwards Total Depth 4000 Oil Well Gas Well X Input Well  SWD Well  D & A  Lost Hole Mr. Smith was instructed to plug the well as follows:

315' of 10 3/4" surface pipe, cement circulated. 3974'  
of 6 5/8" drill pipe for long string, cemented with 125  
sacks. Plugged back to 3865'. Top perforation 3691'. Sand  
to 3670', cement with 5 sacks. Fill hole with mud to 275',  
10' rock bridge, cement with 30 sacks. Fill hole with mud  
to 40', 10' rock bridge, cement with 15 sacks to base cellar.  
 Very truly yours,

Archie Elving  
 Conservation Division Agent