

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 4 1970
 3-4-70
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Buffington of Red Tiger Drlg. Co. has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Co.

Complete Address: 411 1st Natl. Bank Bldg. Wichita, Ks

Lease Name: Neiding Well No. 2

Location: SE/SE/SE Sec. 1 Twp. 24 Rge. 16 (E)(W)X

County: Edwards Total Depth 4055 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:
210 ft of 8 5/8 surface pipe circulated with 200 sacks
cement. Fill hole to 975 ft, plug, 25 sacks cement. Mud to
210 ft, plug, 25 sacks cement. Mud to 40 ft, 1/2 sack hulls,
plug, 10 sacks cement to top of surface. 2 sacks cement
in rat hole. Plugged with pump truck.

Very truly yours,

D Russell Beuten
 Conservation Division Agent