

State of Kansas



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 3-18-68  
 MAR 18 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Ray Steckoll of Wichita Iron & Metal has this  
 date requested permission to plug the following described well:

Mr. Ray Steckoll guarantees payment of the plugging fee.

Operator's full Name: Wichita Iron & Metal

Complete Address: Box 2421, Wichita, Kansas 67202

Lease Name: Koelsch "B" Well No. # 2

Location: SW NW SW Sec. 11 Twp. 24 Rge. 14 (E)(W) W

County: Stafford Total Depth 4050 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ralph Glenn was instructed to plug the well as follows:

8 5/8" 221' Cwc.

Sanded hole back to 3550' & dumped 5 sax cement with dump bailer.

Pulled pipe. Set plug @ 215' & displaced 6 sax cement. Let set

over night. Bailed hole dry & displaced 25 sax cement. Mud to 40'.

set rock bridge, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don L. Linn  
 Conservation Division Agent