

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

February 3, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. John Armbruster of B & B Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Petroleum, Inc.

Complete Address: 800 H.R. Garvey Bldg., Wichita, Kansas 67202

Lease Name: Rixon "A" Well No. 3

Location: 150' E of C NE SW SW Sec. 7 Twp. 24 Rge. 13 (W)

County: Stafford Total Depth: 4186'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Armbruster was instructed to plug the well as follows:

8 5/8" - 298' - 225 sacks Common. Fill hole with mud. Pump 50 sacks Cement through drill pipe at 700'. Pump 25 sacks Cement through drill pipe at 290'. Fill hole with mud to 40'. Push plug and 1/2 sack bulls to 40' and cap hole with 10 sacks Cement. Cement rat-hole with 5 sacks Cement. (50-50 Permiz w/4% gel and 3% Cal. Chloride)

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
2-11-81
FEB 11 1981

CONSERVATION DIVISION
Wichita, Kansas