

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAR 14 1966

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Sun Oil Company

Operator's full Name: Rains & Williamson Oil Co., & Sam P. Wallingford, Inc

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Luther Well No. # 1

Location: C NW SW Sec. 15 Twp. 29 Rge. 14 (E) (W) W

County Pratt Total Depth 4610' Oil Well

Gas Well Input Well SWD Well D & A  Lost Hole

Mr. Walker was instructed to plug the well as follows:

431' of 8 5/8" surface pipe, cement circulated with 250 sacks.  
Fill hole with drilling mud to 300', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Aubie Elving*