



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 28, 1963

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

6-3-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Otto Berens of Rex & Morris Drilling Co. has this
date requested permission to plug the following described well:

Mr. Berens guarantees payment of the plugging fee.

Operator's full Name: Rex & Morris Drilling Company

Complete Address: Box 334, El Dorado, Kansas

Lease Name: Miller Well No. 1

Location: NE NE NE Sec. 10 Twp. 22 Rge. 10 (E) (W) X


County Reno Total Depth 3610' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Berens was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 200'. Push
plug and 1/4 sack hulls to 200' and cement with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push plug
and 1/4 sack hulls to 35' and cap hole with 10 sacks.
Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent