

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

May 30, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 06 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Ed Porter of Pyron Exploration & Drllg has this
date requested permission to plug the following described well:

Mr. Porter guarantees payment of the plugging fee.

Operator's full Name: Pyron Exploration & Drilling Corporation

Complete Address: P.O. Box 236, Rockwall, Texas

Lease Name: Sankey "C" Well No. 1

Location: NW NE SW Sec. 13 Twp. 22 Rge. 10 (E) (W) X

County: Reno Total Depth 3732' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Porter was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe

at 500'. Pump 25 sacks cement through drill pipe at 195'.

Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William J. Lomen
Conservation Division Agent