



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 24, 1963

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

MAY 29 1963
 5-29-63
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Olson of Duke Drilling Company has this

date requested permission to plug the following described well:

Mr. Olson guarantees payment of the plugging fee.

Operator's full Name: Duke Drilling Company

Complete Address: Box 823, Great Bend, Kansas

Lease Name: Schweizer Well No. 1.

Location: SE SE SE Sec. 21 Twp. 22 Rge. 10 (E) (W) X

County Reno Total Depth 3681' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Olson was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 265'. Push
plug and 1/2 sack hulls to 265' and cement with 20 sacks
through drill pipe. Fill hole with mud to 40'. Push
plug and 1/2 sack hulls to 40' and cap hole with 10 sacks.
Bridge rathole, and cement with 2 sacks.

Very truly yours,


 Conservation Division Agent