

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 10, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1966
7-21-66

CONSERVATION DIVISION

Dear Sir:

Mr. H. G. Pankratz of H-30 Drilling, Inc. Wichita, Kansas this

date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: H-30 Drilling, Inc.

Complete Address: 200 North Main, Wichita, Kansas

Lease Name: Sankey Well No. 1

Location: NW NW NW Sec. 23 Twp. 22 Rge. 10 ~~(E)~~ (W) X

County Reno Total Depth 3682' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

Fill hole with mud to 265'. Push plug and 1/4 sack hulls to 265' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent