

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-155-00006-00-01

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

June 6, 1964

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

JUN 12 1964  
6-12-64  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Albert Shiffner of Forbes Casing Pulling Inc. has this date requested permission to plug the following described well:

Mr. Shiffner guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc.

Complete Address: Box 486, Great Bend, Kansas

Lease Name: Swanson Well No. 1

Location: NE NW SW Sec. 1 Twp. 23 Rge. 5 (E) (W) X

County Reno Total Depth 4029 Oil Well Washdown

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Shiffner was instructed to plug the well as follows:

Push 5½" plug to 3820'. Fill hole with sand to 3800' and cement with 5 sacks. Fill hole with mud to 710'. Set rock bridge from 710' to 700' and cement with 20 sacks. Fill hole with mud to 210'. Set rock bridge from 210' to 200' and cement with 20 sacks. Fill hole with mud to 40'

Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,