

15-155-20812-00-00

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

July 26, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG - 3 1981
8-3-81
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Jim Moore of Brandt Drilling Co., Inc. has this

date requested permission to plug the following described well:

Operator's Full Name: McGinnes Oil Company

Complete Address: 1026 Union Center Bldg, Wichita, Kansas 67202

Lease Name: Swanson Well No. 1

Location: SE SW SW Sec. 1 Twp. 23 Rge. 5 (E) (W)

County: Reno Total Depth: 3977'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated:

Mr. Moore was instructed to plug the well as follows:

Circulate hole and Fill With mud. Pump 25 sacks 60-40 Pozmix with
3% Cal. ch. Through drill pipe at 800'. Leave set For 3 hours
Pump 180 sacks cement Through drill pipe on cement at 600'
(Circulate and Fill hole Full of cement) Cement rat hole with 10 sacks
Cement.

854-805-400 sacks circ. (Salt mine mining area Salt protected.)

Very truly yours,

Philip J. Larson
Conservation Division Agent