

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY O. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1965  
1-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jack Gabbert of Gabbert-Jones Inc. has this  
date requested permission to plug the following described well:

Mr. Gabbert guarantees payment of the plugging fee.

Operator's full Name: O. A. Sutton

Complete Address: 407 Insurance Bldg., Wichita, Kansas

Lease Name: Blackburn Well No. # 1

Location: App. C NW NE Sec. 9 Twp. 24 Rgs. 12 (E) (W) W

County Stafford Total Depth 3905 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Gabbert was instructed to plug the well as follows:

242' of 8 5/8" surface pipe, cement circulated with 225 sacks.

Fill hole with drilling mud to 225', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent