



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

July 3, 1970
RECEIVED
STATE CORPORATION COMMISSION
7-10-70
JUL 10 1970
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: J. A. Allison

Complete Address: 1415 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Kiem Well No. 1

Location: C NE NW Sec. 27 Twp. 24 Rge. 5 (W) X

County: Reno Total Depth 3828' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lahar was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and
cement hole with 35 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 15
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent