

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
8-12-75
AUG 12 1975CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg has this
date requested permission to plug the following described well:Mr. Cameron guarantees payment of the plugging fee.Operator's full Name: Graves Drlg IncComplete Address: 910 Union Center Wichita, KSLease Name: Owen Well No. 1Location: G W/2 SW/SE Sec. 3 Twp. 24s Rge. 14 (E)(W)WCounty: Stafford Total Depth 3589 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Cameron was instructed to plug the well as follows:260 ft 8 5/8 surface cemented with 200 sacks. Pump plug,35 sacks cement to 230 ft. Mud to 40 ft, plug, 1/2 sackhulls, 15 sacks cement to surface. 2 sacks cement inrat hole.Pumped by Sun Cementin Great Bend, KS

Very truly yours,