

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 11 1965
 1-11-65
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Wayne Dobbs of Vaughan Drilling Inc. has this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: Vaughan Drilling Inc.

Complete Address: Box 825, Great Bend, Kansas

Lease Name: Garey Well No. # 1

Location: NW NW SE Sec. 22 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4109 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

236' of 8 5/8" surface pipe, cement circulated with 190 sacks.

Fill hole with drilling mud to 225', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling

mud to 40', 2nd cementing plug, bridge with hulls, and cement

with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent