

KANSAS

Form CP-3  
Rev. 6-26-62STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORTJ. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION  
5-26-66  
MAY 26 1966CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Stickle Drilling Company

Complete Address: 1100 Bitting Bldg., Wichita, Kansas

Lease Name Mershon Well No. # 1

Location NW NE SE Sec. 16 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4115'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 25th Month May Year 1966

## The Above well was plugged as follows:

269' og 8 5/8" surface pipe, cement circulated. 4114' of 4 1/2" long string,  
cemented with 100 sacks. Plug back T.D. 4016'. Top perforation 3896'.

Bottom of the hole was sanded to 3875', and cemented with 3 sacks, through  
the dump bailer. 3450' of 4 1/2" long string was recovered from the hole.

Fluid in the hole was bailed down to 250', bridge plug and rock bridge  
from 250' to 240', and cemented with 25 sacks. Hole was filled with mud  
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the  
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging SupervisorDATE 5-26-66INV. NO. 3282-w