

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 211 North Broadway  
 Wichita, Kansas

FILE NO. 106-45LOCATION SW-7E-7WSEC. 11 TWP. 24 RGE. 12 WDry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 4 Lease HildebrandOperator Herman Geo. Kaiser Address 909 Palace Bldg Tulsa Okla.Field \_\_\_\_\_ County StephensTotal Depth 3812 Feet.Plugging Contractor R & S Pipe Pulling Co.Plugging Contractor's License No. 1Address Ellinwood, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 200' c.w.c. 5 1/2" O.D. casing  
set 3811' w/ 125' ss Cem. Sanded hole to 3800'  
dumped 5' ss Cem. Shot off and pulled 5 1/2"  
Casing. Filled hole with heavy mud to  
325' set rock bridge and run 20' ss Cem.  
mud to 35' rock bridge & 10' ss Cem. to  
base of cellar

Warren H. Horner  
 District Conservation Agent

Date May 26, 1955

RECEIVED  
 STATE CORPORATION COMMISSION  
 5-30-55  
 MAY 30 1955

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 11 T 24 R 12W  
 BOOK PAGE 106 LINE 45