

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

R

API Number 15-155-20,809-000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Holt Oil & Gas Corporation

Complete Address 8150 N. Central Expwy., Suite 1255, Dallas, Texas

Lease Name Holt-Hempstid Well No. 1

Location SE SW NE Sec. 35 Twp. 23 Rge. 5 (~~East~~) (West)

County Reno Total Depth 3910'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor H-30 Drilling, Inc. and Allied cementing Co., Inc.

Address 251 N. Water, Wichita, Kansas License No. _____

Operation Completed: Hour: 8:30 AM Day: 18 Month: July Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-287'-175 sacks circ.

Hole circulated and filled with mud. 50 sacks 50-50 Pozmix w/4% gel
and 3% cal. chl. pumped through drill pipe at 520'. 40 sacks cement
pumped through drill pipe at 280'. Hole filled with mud to 40'. Plug
and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar.
with 10 sacks cement. Rathole cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
7-23-81
JUL 23 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-25-81

INV. NO. 6248-W

Signed: *Arthur J. Johnson*
Conservation Division Agent

127.08