

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 122-34
LOCATION SE-SW-SW
SEC. 12 TWP. 24 RGE. 14 W

Dry Hole Abandoned Oil Well ✓ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Shell "B"

Operator Cities Serv. Oil Co. Address Box 751, St. Bend, Ks.

Field County Stafford

Total Depth 3875 Feet.

Plugging Contractor Walker Drly Inc. & Chas D. Wilson

Plugging Contractor's License No. ?

Address Great Bend, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" (A) 370' c.w.c. 5 1/2" set 3875'
w/ 125 sv Cem. Baker plug at 3703' top perf. 3643'
Sand to 3630' dumped 2 sv Cem. Shot off
and pulled 5 1/2" casing. Pumped 20 sv mud
plug & 100 sv Cem. by Halliburton Cem. Co.
Filling surface pipe from 300' to base of
cellar with Cem.

RECEIVED
STATE CORPORATION COMMISSION
7-5-55
JUL 5 - 1955

Warren H Harner
District Conservation Agent

Date July 3, 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 12 T 24 R 14 W
BOOK PAGE 122 LINE 24