

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1964
6-15-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name E. H. Riggs

Complete Address: 1107 Union Nat'l Bank Bldg., Wichita, Kansas

Lease Name Brown Well No. 1

Location SE SE NW Sec. 12 Twp. 22 Rge. 10 (E) (W) X

County Reno Total Depth 3227'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4 PM Day 11 Month June Year 1964

The Above well was plugged as follows:

5½" plug pushed to 3110'. Hole filled with sand to 3100' and cemented
with 5 sacks. Hole bailed to 210'. Rock bridge set from 210' to
200' and hole cemented with 20 sacks. Hole filled with mud to 40'.
Rock bridge set from 40' to 30' and hole cemented to base of cellar
with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/15/64
INV. NO. 9305-W

Signed: [Signature]
Well Plugging Supervisor