

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

RECEIVED
STATE CORPORATION COMMISSION
(of this 1978)
JUL 31 1978
7-31-78
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Bldg., Russell, Kansas 67665

Lease Name Proffitt Well No. 1

Location NE NW NE Sec. 12 Twp. 22 Rge. 10 ~~W~~ (W) X

County Reno Total Depth 3625'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 10:00 AM Day 27 Month 7 Year 1978

The above well was plugged as follows:

Sanded Back to 3100' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

25 sx mud gel, plug, and 100 sx cement.

Max pres. 600#. Shut in Pres. 250#.

Plugged back to 3130'. Tpp perf. at 3119'.

Recovered 2600' of 5 1/2" casing.

3197' of 5 1/2" casing cemented with 75 sx cement.

205' fo 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-31-78
INV. NO. 7762 W

Signed: [Signature]
Well Plugging Supervisor