

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-155-20,514-0000

245 North Water
Wichita, KS 67202

Operator's Full Name Kelso Casing Pulling

Complete Address Box 176, Chase, Kansas 67524

Lease Name Sankey "A" Well No. 1

Location NE NE NW Sec. 13 Twp. 22 Rge. 10 (~~East~~) (West)

County Rice Total Depth 4435'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Operator

Address _____ License No. 683

Operation Completed: Hour: 5:30 PM Day: 27 Month: January Year: 1981

The above well was plugged as follows: 8 5/8" - 214' - cem. circ - 5 1/2" - 3250 - 100 sacks
Push plug to 3250' Filled hole with sand to 3200' and
Cemented with 5 sacks. Bailed hole to 214' set rock bridge
From 214' to 200' and cemented hole with 25 sacks cement.
Filled hole with mud to 40' set rock bridge From 40' to 30'
and cemented hole From 30' to cellar with 10 sacks cement,
2045' of 5 1/2" casing recovered.

1-30-81

JAN 30 1981
CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]
Conservation Division Agent

DATE 2-18-81

INV. NO. 4496-W