

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- -

245 North Water
Wichita, KS 67202Operator's Full Name Kelso Casing PullingComplete Address Box 176, Chase, Kansas 67524Lease Name Sankey "D" Well No. 1Location SW SW SW Sec. 13 Twp. 22 Rge. 10 (~~E~~) (West)County Reno Total Depth 3700'Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☐

Other well as hereafter indicated _____

Plugging Contractor OperatorAddress _____ License No. 683Operation Completed: Hour: Noon Day: 6 Month: February Year: 1981The above well was plugged as follows: 8 7/8" - 220' cc 5 1/2" - 3694' - 200 sacks P8TD - 3550 Top A/F. 3520'Hole Filled with sand to 3250' and cemented with 5 sacks cement.Hole bailed to 210' Rock bridge set from 210' to 200' and holecemented with 25 sacks cement. Hole Filled with mud to 40'.Rock bridge set from 40' to 30' and hole cemented to baseof cellar with 10 sacks cement.1720' of 5 1/2" casing recovered.RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1981 2-11-81

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-4-81INV. NO. 4767-WSigned: [Signature]
Conservation Division Agent