

15-155-00006-00-01

Form CP-3
Rev. 6-26-62

99

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1964
6-12-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leben Drilling Inc.

Complete Address: Box 486, Great Bend, Kansas

Lease Name Swanson Well No. 1

Location NE NW SW Sec. 1 Twp. 23 Rge. 5 (E) (W) X

County Reno Total Depth 4029'

Abandoned Oil Well Gas Well Input Well SWD Well Washdown
D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:30PM Day 9 Month June Year 1964

The Above well was plugged as follows:

5 1/2" plug pushed to 3820'. Hole filled with sand to 3800' and cemented
with 5 sacks. Hole filled with mud to 710'. Rock bridge set from 710'
to 700' and hole cemented with 20 sacks. Hole filled with mud to 210'.
Rock bridge set from 210' to 200' and hole cemented with 20 sacks.
Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole
cemented to base of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-12-64

INV. NO. 9293-W

Signed: [Signature]
Well Plugging Supervisor