

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form GP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 16 Twp. 24 Rge. 12 (E) W (W)
NW NE SE

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines _____
 Lease Owner Stickle Drilling Company
 Lease Name Mershon Well No. 1
 Office Address Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced 5-23-66 _____ 19____
 Plugging completed 5-25-66 _____ 19____
 Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4115 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	269'	None
				4-1/2"	4114'	3437'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to plug-back @ 4016', sanded to 3875' and dumped 3 sacks of cement @ 3875' with dump bailer. Pulled 4 1/2" casing, bailed fluid to 250', set rock bridge to 240' and dumped 25 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
6-2-66
JUN - 2 1966

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
 Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1966

My commission expires May 20, 1968
Milton J. Volin
 Notary Public.

#623-X1

Stickle Drilling Company
Wichita, Kansas

Tulsa, Oklahoma
April 1, 1963

Contractor: Stickle Drilling Company
Date Commenced: March 18, 1963
Date Completed: March 28, 1963

Mershon No. 1
NW NE SE Sec. 16-24S-12W
Stafford County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Sand and shale	165
Shale and shells	271
Red bed and shale	860
Shale	1770
Lime and shale	2010
Shale and lime	2560
Lime and shale	2790
Shale and shells	3085
Shale and lime	3217
Lime	3360
Shale	3385
Shale and lime	3614
Lime	3803
Lime and shale	3890
Lime	3908
Lime and chert	3980
Lime	4082
Chert and lime	4087
Arbuckle	4105
Lime	4112 TD


RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1966

STATE CORPORATION COMMISSION
Tulsa, Oklahoma

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Stickle Drilling Company's Mershon No. 1, NW NE SE of Sec. 16-24S-12W, Stafford County, Kansas.


Fred E. Stickle


Public


2277, 2287