

TATE OF KANSAS  
 TATE CORPORATION COMMISSION  
 30 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-02-3-117

API NUMBER 15-185-22.807

LEASE NAME Teichman

WELL NUMBER 1

4950 Ft. from S Section Line

4290 Ft. from E. Section Line

SEC. 17 TWP. 24 RGE. 12W (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 9-15-00

Plugging Completed 9-19-99

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Rama Operating Co., Inc.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3882'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	261'	None
				5-1/2"	3866'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 3500' and 5 sks. cement. Shot pipe @2600', 2400', 2200', pulled up to 700', pumped 10 sks. gel and 50 sks. cement, pulled up to 290', pumped 50 sks. cement, pulled to 40', pumped 10 sks. cement, topped off with 10 sks. 60/40 nos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator/Char. K Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of September, 2000

[Signature]  
 Notary Public

My Commission Expires: \_\_\_\_\_



Form CP  
 Rev. 1-8-05