

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 209 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-185-22,119-0001

LEASE NAME Newell

WELL NUMBER 1-31

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 31 TWP. 24N RGE. 11 (W) (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-22-95

Plugging Completed 2-22-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Arrow Oil & Gas Inc.

ADDRESS PO Box 862- Norman, Ok. 73070

PHONE# (405) 364-3618 OPERATORS LICENSE NO. 31405

Character of Well D&A

(Oil, Gas, D&A SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-20-95 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well-log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 2507

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 STATE CORPORATION COMMISSION  
 T.D. 2507  
 3-13-95  
 MAR 13 1995

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Putted out
		0	2494	8 1/8 4 1/2	2494	1810 ft. - 588 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 50ft. above perts. on 2-21-95. Then dumped 45t cement on top of sand. Sand at 2240. Cut casing at 1810 and pulled out of hole. Rigged down & moved off. Allied Cement top hole plugged the well. (See back of page)  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc. License No. 5893

Address PO Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Arrow Oil + Gas

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO Box, Inc.



SUBSCRIBED AND SWORN TO before me this 8th day of March, 19 95

Dorothy M. Furgason  
 Notary Public

My Commission Expires February 6, 1997

300# hulls - 10 sx. gel - 50 sx. cement - 10 sx. gel -  
100# hulls. 8 5/8 plug - 100 sx. cement. 60-40 poz. 6% gel.  
850# max - 200# shut in pressure. 16 ft. down to top  
of cement from surface.