

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15185-00809-0001

LEASE NAME Irvine

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 31 TWP. 24 RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed         

Plugging Commenced 3-24-94

Plugging Completed 3-29-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Cincris Energy Company

ADDRESS 22996 El Toro Rd, El Toro, CA 92630

PHONE# (916) 885-0816 OPERATORS LICENSE NO. 9247

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	308'	none
				5 1/2	4154'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Sanded bottom to 4100' & dumped 5 sks cement. Shot @ 3000, 2800, 2600, worked pipe left on tension. Shot @ 2400, 2300, & 2200, pipe came loose. Pulled pipe. Plugged well with 300# hulls, 10 gel, 50 sks cement, 10 gel, 100# hulls, release plug, 100 sks cement. Shut in. 60/40 poz 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Cincris Energy Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 30th day of March, 19 94

Irene Herzberg  
Notary Public

My Commission Expires:         



Form CP-4  
Revised 05-80

RECEIVED  
STATE CORPORATION COMMISSION  
3-31-94  
MAR 31 1994  
CONSERVATION DIVISION  
Wichita, Kansas