


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County. Sec. 11 Twp. 24 Rge. 12 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines



Locate well correctly on above
Section Plot

SE NW NE
Lease Owner PV PROPERTIES, INC.
Lease Name RICHARDSON Well No. 1
Office Address 360 Sutton Place, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole
Date Well completed 3-28 19 81
Application for plugging filed 3-27 19 81
Application for plugging approved 3-27 19 81
Plugging commenced 3-28 19 81
Plugging completed 3-28 19 81
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation Depth to top Bottom Total Depth of Well 3810'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug set at 520' with 50 sacks 50/50 pOzmix thru drill pipe
Middle plug set at 255' w/30 sacks cement thru drill pipe
Top plug at 40' w/1/2 sack hulls f/solid bridge & 10 sacks cement
10 sacks cement in rat hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

BILL DRANEY (employee of owner) or (XXXXXXXXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Draney
Box 823-Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of March, 1981

My commission expires April 11, 1982

Dorothy M. Hogue
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
APR - 1 1981
4-1-81
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

DATE COMMENCED: March 21, 1931
DATE COMPLETED: March 28, 1931

P. V. Properties Inc.
RICHARDSON #2
SE NW NE
Sec. 11, T24E, R12W
Stafford County, Ks.

0	-	135'	Sand
135	-	258'	Shale, Red Bed
258	-	627'	Red Bed, Shale
627	-	650'	Anhydrite
650	-	2950'	Shale & Lime
2950	-	3249'	Lime
3249	-	3254'	Shale
3254	-	3257'	Lime, Shale
3257	-	3262'	Lime
3262	-	3396'	Shale
3396	-	3427'	Lime & Shale
3427	-	3757'	Shale, Chert, Lime
3757	-	3810'	Shale, Lime, Chert
		3810'	RTD

ELEVATION: 1661 K.S.

FORMATION DATA

Anhydrite	627'
Topeka	2950'
Hochstetler	3249'
Toronto	3267'
Douglas	3262'
Br. Lime	3396'
Lansing K.S.	3427'
Mississippi	3714'
Kinderhook	3757'
Viola	3805'
RTD	3810'

Surface Pipe: Set used 28 1/2,
3-5/8" pipe at 258' w/135
sacks 60/40 pozmix, 2 1/2 gal,
3 1/2 cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and
statements herein contained are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 31 day of March, 1931.

My Comm. Expires:

4-11-1932

Victoria M. Wague
Notary Public

APR - 1 1931