


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 11 Twp. 24 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines NW - NW - NE
Lease Owner Herman George Kaiser
Lease Name Richardson Well No. 1
Office Address Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced May 14 19 58
Plugging completed May 19 19 58
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Brodfoot
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203	None
				5 1/2	3800	2867.25

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 3790' - dumped 5 sks cement - pulled pipe -
pumped 20 sks Jel Mud and 75 sks cement in hole.

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
I, W. J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Hall

(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of May 19 58

Delmer R. Postner
Notary Public.

My commission expires

PLUGGING
FILE SEC 11 T 24 R 12W
BOOK PAGE 97 LINE 15

Owner: ~~Archer~~ Drilling Company, Inc.
 Geomembrane: ~~Archer~~ Drilling Company, Inc.
 Drilling Commenced: 3/10/49
 Drilling Completed: 4/7/49
 Elevation: 1858'
 Rotary Rig #2

Survey: Richardson #2
 Location: NW NW NE 11-21-49-12W
 Stafford County, Kansas
 Coring Record: 8-5/8" set @ 203 cemented
 w/200 sacks cement
 5 1/2" set @ 3000 cemented
 w/125 sacks cement

(figures below indicate bottom)

Surface soil	35
Sand	205
Red bed	315
Red bed, shale & shells	610
Anhydrite	660
Shale & shells	1370
Salt, shale & shells	1510
Shale & sand, Fort Riley line	1625
Lime	1830
Shale & lime	1895
Lime	2105
Shale & lime	2360
Shale	2445
Shale & lime	2675
Lime	2820
Lime & shale	3000
Lime	3203
Shale & lime	3376
Shale	3442
Shale & lime	3514
Lime	3692
Shale & lime	3732
Lime	3750
Lime & shale	3790
Lime, Viola	3904
Total Depth - corrected	3903 - Rotary

TOPS:

Kansas City	3455
Viola (corrected)	3900

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARCHER DRILLING COMPANY, INC.

By _____

STATE OF KANSAS)
) ss
 COUNTY OF _____)

Subscribed and sworn to before me, a notary public, in and for said County and State this 13th day of April, 1949.

NOTARY PUBLIC
 COMMISSION

Notary Public

My commission expires Sept. 17, 1951.

STATE DIVISION
 KANSAS

PLUGGING			
FILE	SEC	11 T 24 R 12W	
BOOK	PAGE	97	LINE 15