

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-22893-00-00
Spot: NWNENE Sec/Twnshp/Rge: 1-17S-11W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: ZAJIC Well #: 3
County: BARTON Total Vertical Depth: 3398 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: 314 5TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3388		125 SX
SURF	8.625	280		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/06/2016 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GARY PAULEY Company: PAULEY OIL Phone: (785) 252-8024

Proposed
Plugging
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement, 1400 # gel and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 700' and 250'. Ran tubing to 3288' and pumped 14 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 700'. Circulated cement to surface on casing w/60 sx cement. Pulled tubing. Tied on to casing and circulated cement to surface on surface pipe w/50 sx cement.

GPS: 38.60802 -098.48334

Perfs:

Top	Bot	Thru	Comments
3388	3390		
3102	3104		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSGTB G

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

JAN 07 2016

Form CP-2/3

no
1-15-2016