

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25204-00-00
Spot: SENENWNE Sec/Twnshp/Rge: 23-18S-24W
343 feet from N Section Line, 1636 feet from E Section Line
Lease Name: UMMEL BROTHERS TRUST Well #: 1
County: NESS Total Vertical Depth: 4405 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1515		CEMENTED WITH 145 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	5.5	4391	0	WITH 170 SX CMT
SURF	8.625	224		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2015 2:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: GLENN DINKEL Company: PALOMINO PETROLEUM Phone: (316) 799-1000

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/30/2015 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4250' & PUMPED 35 SX CMT & 150# HULLS. PULL TBG TO 1600' & PUMP 160 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURD TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4306	4308		
4298	4304		

KCC WICHITA
JAN 08 2016
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
JAN 05 2016
KCC DODGE CITY

Signed Michael Maier
JA (TECHNICIAN)

220
1-15-2016
Form CP-2/3