

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23093-00-00
Spot: NWNENESW Sec/Twnshp/Rge: 15-15S-14W
2600 feet from S Section Line, 2200 feet from W Section Line
Lease Name: KRUG L Well #: 1
County: RUSSELL Total Vertical Depth: 3272 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3220		
PROD	5.5	3253	2000	140 SX
SURF	8.625	649		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/24/2015 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS, INC. Phone: (785) 445-2353

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cut casing at 2000' leaving 1253' of 5 1/2" casing and CIBP at 3220'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/24/2015 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

12/23/2015- Sanded back to 2900' and spotted cement on top. Cut casing and pulled up to 1400'.
12/24/2015- Pumped 125 sx cement w/300 # hulls. Pulled casing to 835' and pumped 50 sx cement w/100 # hulls. Pulled casing to 340' and pumped 125 sx cement. Circulated cement to pit. POOH. Cellar stayed full.

GPS: 38.74742 -098.86690

Perfs:

Top	Bot	Thru	Comments
3253	3272		
3186	3189		
3007	3010		
2964	2967		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: QUALITY CEMENTING TICKET # 1313

Plugged through: CSG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

cm