

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21423-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 33-22S-34W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: VOLLMERS Well #: 2
County: FINNEY Total Vertical Depth: 2760 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2757	0	WITH 625 SX CMT
SURF	8.625	301		WITH 260 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/21/2015 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: LEO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2015 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG IS STUCK DUE TO GLORIETTA CASING LEAK. PULL 32000#. STILL STUCK. LOAD TBG & ATTEMPT TO PUMP INTO PERFS AT 1500#. COULD NOT. STRETCH CALCULATIONS SHOW TBG STUCK AT APPROXIMATELY 2100'. CUT TBG AT 1874'. PULLED 40000#. NOT FREE. ATTEMPT TO PUMP INTO CUT AT 2000#. COULD NOT. CUT TBG @ 1208'. TBG FREE. PULL TO 1200' & CIRCULATE CMT TO SURFACE WITH 100 SX CMT. TOOH & TOP OFF WITH 10 SX CMT. PUMP 5 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:


Top	Bot	Thru	Comments
2476	2592		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

KCC WICHITA

JAN 11 2016

RECEIVED

RECEIVED
JAN 06 2016
KCC DODGE CITY

Form CP-2/3

no 1-15-2016