

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-16196-00-00
Spot: NWNWENW Sec/Twnshp/Rge: 2-17S-13W
5145 feet from S Section Line, 3675 feet from E Section Line
Lease Name: GAGE Well #: 1
County: BARTON Total Vertical Depth: 3282 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	2968		100 SX
SURF	8	262		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO OIL Phone: (620) 938-2943

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 1000 # gel and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 760' and 250'. Ran tubing to 2900' and pumped 10 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 65 sx cement w/100 # hulls. Pulled tubing to 760' and pumped water with 200 # hulls. Circulated cement to surface with 100 sx cement. Shut in casing and circulated cement to surface on surface pipe w/60 sx cement. Pulled tubing and topped off w/10 sx cement.

GPS: 38.60781 -098.73240

Perfs:

Top	Bot	Thru	Comments
2897	2905		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Brian Prock
(TECHNICIAN)

CM

No
1-15-2016