

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20551-00-01
Spot: SESESESE Sec/Twnshp/Rge: 36-21S-34W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: MAUNE Well #: 2CG-36
County: FINNEY Total Vertical Depth: 4800 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING,
Address: 1200 MAIN ST PO BOX 818
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1960		
CIBP		2730		WITH 10 SX CMT
CIBP		2980		
DVT		3003		WITH 250 SX CMT
PROD	5.5	4702	0	WITH 550 SX CMT
SURF	8.625	431		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/09/2015 12:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/10/2015 11:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

12/9/15: SET CIBP @ 2730' WITH 10 SX CMT. LOAD & TEST CASING TO 500#. HOLDING. RUN CBL. HOLE LOSING FLUID. FLUID WENT DOWN BELOW 2000'. SET 2ND CIBP @ 1960'. LOAD & TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 470'. BREAK CIRCULATION. SDON. 12/10/15: RUN TBG TO 1921' & SPOT 5 SX CMT PLUG. PULL TBG TO 1134' & CIRCULATE CMT TO SURFACE UP BOTH THE 5 1/2" CASING & THROUGH THE PERFS AT 470' IN THE 5 1/2" X 8 5/8" ANNULUS USING 200 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2780	2796		

KCC WICHITA
JAN 08 2016
RECEIVED

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
DEC 17 2015
KCC DODGE CITY

Signed

SA

Ken Jehlik
(TECHNICIAN)

(TECHNICIAN)

no
1-15-2016