

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20219-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 24-29S-14W
4981 feet from S Section Line, 4953 feet from E Section Line
Lease Name: PERDUE UNIT Well #: 1
County: PRATT Total Vertical Depth: 4350 feet

Operator License No.: 33272
Op Name: JACK HACKER
Address: 30401 SW 90TH ST
COATS, KS 67028

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3750		WITH 2 SX CMT
PROD	4.5	4349	2216	WITH 150 SX CMT
SURF	8.625	408		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/17/2015 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4100' WITH 2 SX CMT. PLUG AT 820' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2015 9:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3750' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 820' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4144	4150		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
5A

(TECHNICIAN)
KCC WICHITA

RECEIVED
JAN 07 2016
KCC DODGE CITY

JAN 11 2016
RECEIVED

Form CP-2/3

20
1-15-2016