

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22394-00-00
Spot: NWNESESE Sec/Twnshp/Rge: 10-27S-12W
1021 feet from S Section Line, 368 feet from E Section Line
Lease Name: BOLEN Well #: 1
County: PRATT Total Vertical Depth: 4600 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3940		WITH 2 SX CMT
PROD	4.5	4106	1600	WITH 200 SX CMT
SURF	8.625	703		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/18/2015 8:30 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: KENNETH C. GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 672-9571

Proposed Plugging Method: CIBP @ 3910' & 2 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2015 10:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3940' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3968	3972		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)

RECEIVED
JAN 07 2016
KCC DODGE CITY

KCC WICHITA

JAN 11 2016

RECEIVED

Form CP-2/3

1-15-2016