

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20316-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 22-10S-25W
3047 feet from S Section Line, 1716 feet from E Section Line
Lease Name: KNOLL A Well #: 1
County: GRAHAM Total Vertical Depth: 3995 feet

Operator License No.: 34657
Op Name: DREILING EXPLORATION LLC
Address: 815 MAIN ST
VICTORIA, KS 67671

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	3.5	3884		110 sx
PROD	4.5	3992		100 SX
SURF	8.625	213		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/23/2015 12:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: PRESTON DREILING Company: DREILING EXPLORATION LLC Phone: (785) 639-2099

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3859' - 3877'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2015 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated casing at 2145' and 1250' (Perf Tech). Hooked to 3 1/2" casing and pumped 75 sx cement followed by 170 sx cement w/350 # hulls. Shut in pressure 400 psi. Hooked to annulus and pumped 5 sx cement. Shut in pressure 300 psi.

GPS: 39.16921N -100.09541W

Perfs:

Top	Bot	Thru	Comments
3872	3877		
3864	3868		
3859	3862		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: QUALITY OILWELL CEMENTING TICKET # 1501

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

no
1-15-2016