

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-24959-00-00
Spot: NESWSWSW Sec/Twnshp/Rge: 1-17S-22W
636 feet from S Section Line, 555 feet from W Section Line
Lease Name: PFAFF Well #: 1-1
County: NESS Total Vertical Depth: 4420 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1583		WITH 200 SX CMT
PROD	5.5	4419	0	WITH 150 SX CMT
SURF	8.625	217		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2015 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING NELSON Phone: (785) 621-2610

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2015 11:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4300' & SPOT 35 SX CMT & 100# HULLS. PULL TBG TO 1600' & PUMPED 160 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4316	4320		

KCC WICHITA
JAN 08 2016
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
SA (TECHNICIAN)

RECEIVED
JAN 05 2016
KCC DODGE CITY

Form CP-2/3

No
1-15-2016