

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25707-00-00
Spot: SENW Sec/Twnshp/Rge: 31-19S-23W
3295 feet from S Section Line, 3197 feet from E Section Line
Lease Name: WICKED WITCH Well #: 6
County: NESS Total Vertical Depth: 4444 feet

Operator License No.: 34839
Op Name: D & J OIL COMPANY, INC.
Address: 4720 W. GARRIOTT
ENID, OK 73703

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1641		WITH 225 SX CMT
PROD	5.5	4428	0	WITH 150 SX CMT
SURF	8.625	218		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/11/2016 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1650' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF WITH CMT. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2016 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4300' & SPOT 35 SX CMT & 100# HULLS. PULL TBG TO 1650' & PUMPED 175 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 5 SX CMT. STAYED FULL. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4384	4394		

KCC WICHITA
JAN 13 2016
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Michael Maier
SA (TECHNICIAN)

RECEIVED
JAN 12 2016
KCC DODGE CITY

20
1-15-2016
Form CP-2/3