

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20141-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 13-20S-23W
4629 feet from S Section Line, 3255 feet from E Section Line
Lease Name: MARANVILLE Well #: 2
County: NESS Total Vertical Depth: 4350 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
PROD	5.5	4346	0	WITH 125 SX CMT
SURF	8.625	256		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2015 1:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5390

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. PERFORATE @ 1450' WITH 50 SX CMT & 100# HULLS. PERFORATE AT 700' & PUMP 80 SX CMT OVER CASING VOLUME.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2015 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CMT CIRCULATED 280' TO SURFACE ON 6/9/08 SET CIBP @ 4300' WITH 2 SX CMT. PERFORATED AT 1450' & PUMPED 50 SX CMT & 100# HULLS WITH TBG. PERFORATED AT 700' & RUN TBG TO 700' & PUMPED 80 SX CMT. DID NOT CIRCULATE. PULLED TBG & PUMPED 65 SX CMT. DID NOT LOAD. SHUT DOWN FOR 30 MINUTES. TOPPED OFF WITH 30 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4340	4349		

KCC WICHITA
JAN 08 2016
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES

Plugged through: TBG

District: 01

Signed Michael Maier
5A (TECHNICIAN)

RECEIVED
JAN 05 2016
KCC DODGE CITY

Form CP-2/3

20
1-15-2016