

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20290-00-00  
Spot: SWNE Sec/Twnshp/Rge: 29-24S-40W  
3269 feet from S Section Line, 2124 feet from E Section Line  
Lease Name: WOOD Well #: 5-29  
County: HAMILTON Total Vertical Depth: 2450 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2444	0	WITH 550 SX CMT
SURF	8.625	542		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2015 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200# HULLS & 100 SX CMT. DISPLACE TO 800' & PRESSURE TO 700#. RUN BOND LOG. PERFORATE AND OR RUN TBG AS NECESSARY.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/22/2015 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 100 SX CMT TO 2347'. DISPLACE WITH WATER TO 850'. PRESSURE TO 500#. HOLDING. RUN BOND LOG FROM 800' TO 0'. TOC BEHIND 4 1/2" CASING IS 58'. RUN TBG TO 819'. CIRCULATE CMT TO SURFACE WITH 55 SX CMT. TOOH & TOP OFF 4 1/2" CASING WITH 5 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:


Top	Bot	Thru	Comments
2343	2347		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)  
KCC WICHITA

RECEIVED  
JAN 06 2016  
KCC DODGE CITY

JAN 11 2016  
RECEIVED

Form CP-2/3

no  
1-15-2016