

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10981-00-01
Spot: W2SEW Sec/Twnshp/Rge: 17-24S-12W
3300 feet from S Section Line, 3640 feet from E Section Line
Lease/Unit Name: TEICHMAN Well Number: 2
County: STAFFORD Total Vertical Depth: 3880 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size feet: 9126.10
Surface Casing: Size 8.625 feet: 224 WITH 200 SX CMT
Production: Size 5.5 feet: 3880 WITH 125 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E16107.1 Date/Time to Plug: 05/28/2002 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3800' & 5 SX CMT. 1ST PLUG AT 750' WITH 50 SX CMT. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/28/2002 2:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3876-3879'. SAND TO 3820' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 750' WITH 10 SX GEL - 50 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 250' WITH 50 SX CMT WITH 100# HULLS MIXED IN. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED

MAY 31 2002
5-31-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICE DATED MAY 29 2002

DATE 5-31-02

INV. NO. 2002061870

Form 17-233