

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23162-00-00  
Spot: NENESWSE Sec/Twnshp/Rge: 15-24S-12W  
1155 feet from S Section Line, 1410 feet from E Section Line  
Lease/Unit Name: STAFFORD WEST Well Number: 2  
County: STAFFORD Total Vertical Depth: 3826 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

Production Casing Size: 5.5 feet: 3805 WITH 90 SX CMT  
Surface Casing Size: 8.625 feet: 269 WITH 190 SX CMT

*\$ 12435*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2003 2:30 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUG AT 650' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/19/2003 3:45 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3660'. TOP PERFORATIONS 3555'. SANDED TO 3500' & 5 SX CMT WITH BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 650' WITH 10 SX GEL - 100# HULLS - 50 SX CMT. 2ND PLUG AT 300' WITH 100# HULLS - 50 X CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
6-24-03  
JUN 24 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2618' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JUN 20 2003  
KCC Dodge City

Signed

*Richard W. Lacey*

(TECHNICIAN)

INVOICED

6-24-03

200.3061.687

*[Signature]*  
Form 2/3