

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22807-00-00
Spot: NENWNW Sec/Twnshp/Rge: 17-24S-12W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: TEICHMAN Well Number: 1
County: STAFFORD Total Vertical Depth: 3882 feet

Operator License No.: 3911
Operator Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 261
Production: Size 5.5 feet: 3866 *126.17*
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/19/2000 12:00:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING Phone: (316) 938-2537

Proposed Plugging Method: SAND TO 3500' WITH 5 SX CMT. 1ST PLUG AT 700' WITH 50 SX CMT & 10 SX GEL. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/19/2000 1:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3552-3721. SAND TO 3490' & 5 SX CMT. PUMPED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 700' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION
9-26-00
SEP 26 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 9/29/00
200/060767

SEP 22 2000

Form 08-03