

To: 1 121018  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22,119-0001  
NW NE SW, SEC. 31, T. 24 S, R. 11 W  
2310 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31405  
Operator: Arrow Oil & Gas, Inc.  
Name & Address: P.O. Box 862  
Norman, OK 73070

Lease Name Newell Well # 1-31  
County Stafford  
Well Total Depth 2507 81.48 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address: P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 4:30 p.m. Day: 22 Month: 2 Year: 1995

Plugging proposal received from Danny Thompson

(company name) Arrow Oil & Gas Inc. (phone) 405-640-0489

Work: 4 1/2" at 2494' w/150 sx cement, CBP at 2350', Perfs at 2356-60, 2334-40'  
1st plug sand back to 2280' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:45 p.m. Day: 22 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 2280' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Pumping pressure 0-600 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovery 1800' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
(If additional description is necessary, use BACK of this form.)  
observe this plugging.

DATE 3-6-95  
INV. NO. 42326

Signed Richard Lacey  
(TECHNICIAN)