

11-15

1 040190

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-22.119-0000

NW-NE-SW, SEC. 31, T 24 S, R 11 W/E  
2310 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3476  
Operator: Moff Oil Company  
Name & Address 318 North Ninnescah  
Pratt, KS 67124

Lease Name Newell Well # 1-31  
County Stafford 134.06  
Well Total Depth 4125 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 15 Month: 11 Year: 19 88

Plugging proposal received from Ted Moff  
(company name) Moff Oil Company (phone) 316-672-7383

were: 4 1/2" at 4110' PBSD 4050' Perfs at 3853-57, 3512-16, 3681-84'

1st plug sand back to 3460' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 a.m. Day: 15 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3460' and dumped 4 sx cement on top of  
sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, and 100 sx cement.

Maximum pressure 700 psi and shut in 300 psi.

Remarks: Used Halliburton lite cement by Halliburton. Recovered 2400' of 4 1/2" casing.  
(If additional description is necessary, use 'BACK' of this form.)

INVOICED

DATE 11-22-88  
OBSERVE THIS PLUGGING.

INV. NO. 23076  
11-15

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
NOV 17 1988

Signed Stephen J. Pfeifer  
(TECHNICIAN)

JAN 06 1989